

ROCKWOOD WATERLINES

QUARTER 1 - 2023


SPRING IS COMING - IS YOUR SYSTEM READY?

Spring is just around the corner, it's important (& required) to have properly functioning and annually tested backflow protection installed on all underground irrigation systems. If you are unsure if yours is in compliance, please contact our staff for guidance on Oregon Health Authority administrative rules and Rockwood Water PUD policy.

Questions? Contact our Backflow Department via phone at 503-674-4510 or via email at backflow@rwpud.org.

More information regarding backflow protection, specification requirements and a FAQ can be found on our website www.rwpud.org/backflow/.


BUDGET COMMITTEE - SPOTS AVAILABLE



Applications are available at the District office, 19601 NE Halsey Street, Portland, Oregon; on our website at www.rwpud.org under "What's New;". Applications must be received by 5:00 p.m. on March 14, 2012. *No prior experience is needed to apply*.

ELECTIONS RESULTS FOR ROCKWOOD WATER





Two members of the District's Board of Directors were re-elected to their positions on November 3, 2022.

Subdistrict #2: Colby Riley Subdistrict #5: Larry Dixon

Their terms are January 1, 2023 through December 31, 2026. Information about Board members and a map of subdistricts can be found on our website at rwpud.org/board-of-directors.



ROCKWOOD WATERLINES

QUARTER 1 - 2023

CASCADE GROUNDWATER ALLIANCE PROJECT UPDATES

Cascade Well 8 (311 NE 141st)

Well development is completed. Designs have begun on the water treatment facility, well house & reservoir improvements. Site improvement construction (Package 3) is scheduled for 2024.

Package 1 (NE 202nd Avenue, 19601 NE Halsey St, & Surrounding Area)

Cascade Reservoir 2 (CR2) improvements are nearly complete. The reservoir will be tested and commissioned in February. The Cascade Well 7



Cascade Reservoir 2. Photo taken January 10, 2023

(CW7) and 36" groundwater Transmission Mains (TM) will be completed late this winter.

Package 6*: Kirk Park (CW9) wellhouse and TM. Construction will begin soon.

Upcoming Projects:

Package 2A: Design for a TM to move water to and from the 141st Pump Station (PS) has begun. Construction to begin in the fall of 2023.

Package 2B*: Design is wrapping up and will be advertised for construction in late winter. This is for a 36" TM from the District office location to approximately 202nd & Division, to supply finished groundwater to the District's Bella Vista reservoir and Gresham's Grant Butte reservoir.

Package 3: Design has begun for a 2-4 million gallon per day (MGD) treatment facility, reservoir upgrade and new wellhouse construction for our NE 141st Avenue site. Construction is scheduled for 2024.

Package 4: Design for Package 4 has begun. Package 4 is a 25-30 MGD treatment facility and PS upgrade, located at the District office location, on Halsey. Construction will begin in late 2023.

Package 5*: Drilling for a production well (CW6), near Stark & NE 223rd Ave, has begun and will be completed early in 2023. Design for a wellhouse and treatment facility will begin in 2023.

*City of Gresham Managed Project



CONSERVATION TIPS

Check for Leaks

Two common places leaks occur are in the garage or crawl space where the cold air can reach. It's important to check for leaks regularly, especially after major weather events.

Not sure how to check for leaks?

Rockwood offers free tools to help test for leaks and offers a leak adjustment program.

Learn more here:

https://rwpud.org/meter-info/ https://rwpud.org/leak-adjustments/